

ESTIMATE

neatMon, Inc.

7672 Avianca Dr Ste D-40

Redding, CA 96002

info@neatmon.com

+1 (844) 321-6328

http://www.neatmon.com



Bill to

Sierra Valley Groundwater Management

District

PO Box 88

Chilcoot, CA 96105 USA

Estimate details

Estimate no.: 3453

Estimate date: 10/14/2026

#	Date	Product or service	SKU	Description	Qty	Rate	Amount
1.				Location adjustments for the following locations: 13 pivot locations (Grissom 1, Goodwin 3, DS Ranch 4, Roberti 5) Note regarding third-party equipment, testing, and repairs This quotation is limited to the physical relocation and reinstallation of existing third-party monitoring equipment and associated sensor cabling. neatMon does not provide testing, calibration, diagnostics, commissioning, or verification of the functionality, accuracy, or operational condition of third-party monitoring equipment or sensors under this scope of work. All existing equipment and cabling will be relocated and reinstalled in their current condition. neatMon makes no representation or warranty regarding the performance, functionality, or continued operation of this equipment following relocation. Any troubleshooting, repairs, replacement components, additional cabling, or corrective work identified before, during, or			

after installation are expressly excluded from this quotation. Such work, if requested and authorized, will be performed separately on a time-and-materials basis, subject to the availability of necessary equipment, technical information, and replacement parts.

neatMon is not responsible for pre-existing defects, third-party equipment failures, or damage resulting from livestock, agricultural operations, machinery, inadequate protective barriers, or other causes outside neatMon's control. This exclusion does not apply to damage directly caused by neatMon's negligent handling or installation.

2.	FIELD-SERVICE - Advanced Field Services	FIELD-SERVICE	Move third party station to new pole, dig up sensor cabling and install in conduit	13	\$450.00	\$5,850.00
			Any repairs needed to cabling will be charged on a time and materials basis.			
			Node will be located above 6 feet from ground level, or at length determined by length of cabling.			
3.	MISC-HWR - MISC Hardware	MISC-HWR	12-Gauge 1-5/8 in. x 10 ft. Strut Channel, Silver.	13	\$40.00	\$520.00
			Knock out lower slot to attach non-metallic with coupler.			
			Buried 3ft into ground.			
4.	Misc	Misc-HWR	Five foot section of 3/4" flex non-metallic conduit.	13	\$20.00	\$260.00
			Includes 90 degree coupler to attach to strut knock out.			

Subtotal	\$6,630.00
Sales tax	\$56.55
Total	\$6,686.55

Accepted date

Accepted by